

Sports Authority of India
Lakshmibai National College of Physical Education
Trivandrum

F No. 101/LNCPE/Infra/CCTV/2018

Date :03.05.2018

CORRIGENDUM-II

Sub: Installation of CCTV at LNCPE

Ref: 1) Bid No- LNCPE/INFRA/CCTV/2018
2) Tender ID – 2018_SAI_327857_1

- I. In continuation to the Corrigendum – I, the specifications given in page no. 42 of the tender document is further amended and as shown hereunder.

Corrigendum - I			Amended (Corrigendum-II)	
Sl. No.	Particulars	Quantity	Particulars	Quantity
7.	Supply, Installation, Testing & Commissioning of 4 TB SATA HDD (Brand : WD, Seagate, Toshiba)	29 No.s	Supply, Installation, Testing & Commissioning of 4 TB SATA HDD (Brand : WD, Seagate, Toshiba)	36 No.s
10.	Supply, Installation, Testing & Commissioning of PoE – DGS 26MP Gigabit switch	1 No.s	Supply, Installation, Testing & Commissioning of PoE plus – DGS 24 P Gigabit switch with 2 SFP Module compatibility.	8 No.s
11	Supply, Installation, Testing & Commissioning of PoE – DGS 16P Gigabit switch	7 No.s	Item has been deleted.	
12	Supply, Installation, Testing & Commissioning of PoE – DGS 8P Gigabit switch	5 No.s	Supply, Installation, Testing & Commissioning of PoE – DGS 8P Gigabit switch with 2 SFP Module compatibility.	8 No.s

- II. The following new items are also included in the Annexure - I

Sl. No.	Particulars	Quantity
22.A	Supply, Installation, Testing & Commissioning of SFP Module	20 No.s
22.B	Supply, Laying, Termination, Testing & Commissioning of unarmored Single Mode OFC (Optical Fibre Cable) with staywire : 12 - Fibre	700 mtr
22.C	Supply, Laying, Termination, Testing & Commissioning of unarmored Single Mode OFC (Optical Fibre Cable) with staywire : 6 - Fibre	150 mtr
22.D	Supply, Laying, Termination, Testing & Commissioning of armored Single Mode OFC (Optical Fibre Cable) : 12 - Fibre	300 mtr
22.E	Supply & Laying of HDPE(High-Density Poly Ethylene) Pipe	300 mtr
22.F	Supply, Laying, Testing & Commissioning of Underground armored XLPE insulated Power Cable with cable tie, cable tag, termination : 3 core x 1.5 sqmm	500 mtr
22.G	Cable trench with 750mm depth, sand filling above & below cables, laying of bricks & backfilling.	500 mtr
22.H	Tar cutting, excavation of 900mm depth, laying of Hume Pipe (NP-2), backfilling & repairing of road with RCC (100mm thickness) for laying of cables.	80 mtr

- III. Serial numbers of last two items in Annexure-I of Corrigendum-I, i.e. 22 & 23 is changed to 24 & 25 respectively.

Note:

- 1) The rate quoted should be inclusion of installation charge
- 2) The rate to be quoted as per price schedule at Section IV (B)
- 3) The quantity may vary $\pm 25\%$ on actual execution.